POP
Installation planning

Coordinate the kitchen, equipment and services as one project. Utility locations are not universal.

Confirm support points, leveling, arrangement and site suitability for the project.

1 / Composition and equipment

Confirm the layout, final dimensions, appliance models, sink and tap. Equipment is specified separately unless expressly included in the quotation.

2 / Utilities and ventilation

Provide water, drainage, power and gas positions as required by the equipment. Coordinate cutouts, ventilation, service access and connections with the project and appliance manufacturer’s instructions.

3 / Site and delivery

Check the ground’s load capacity and level, delivery access, transport sections, unloading equipment and maintenance clearance. Confirm support and leveling with Evoluta.

4 / Final approval

Use the approved dimensioned drawing before production and site work. Qualified trades carry out connections; the quotation defines delivery, unloading, assembly and utility work.

Your project contact

Evoluta d.o.o.
sales@evoluta.hr | +385 99 836 7145
Vukovarska 19, 52440 Poreč, Croatia

For initial planning only; not a manufacturing or installation drawing. Evoluta confirms final dimensions and details for each project.